

Quotation

No. ⁵⁶⁵ /EE /VHE&LIDB/Ambadi Lab/2022
Office of the Executive Engineer, Vidarbha Hydro
Electric & Lift Irrigation Division, Administrative
building, National Highway No.6, Bhandara,
Email- eevhelidb@gmail.com
Date - 12/06/2022

To,

Notice Board

Subject: - Quotation for the work of Additional work of Providing 3 Phase supply and Internal Electrification to Quality control LAB at Ambadi, Dist. Bhandara

Quotation are hereby invited by the Executive Engineer, Vidarbha Hydro Electric & Lift Irrigation Division, Bhandara the work of Additional work of Providing 3 Phase supply and Internal Electrification to Quality control LAB at Ambadi, Dist. Bhandara


The quotations shall reach to this office on or before from 16/06/2022 to 23/06/2022 up to 15.00 hrs. and will be opened on same day if possible.

Sr.No	Description of Work	Qty	Unit	Rate	Amount
1	Supplying erecting and marking four pole isolators only switch version of miniature circuit breakers of 40A in provided distribution board complete.	3	Each		
2	Supplying and erecting PVC Surface modular switch box with double mounting plate for 3 modules duly erected.	15	Each		
3	Supplying and erecting ISI mark modular type switch 16A duly erected on provided plate and box with wiring connections complete.	15	Each		
4	Supplying and erecting ISI mark modular type 3 pin 6 / 16A multi socket with safety shutter, duly erected on provided plate and box with wiring connections complete.	15	Each		
5	Supplying and erecting exhaust fan heavy duty 230 V A.C. 50 cycles 450 mm. 1400 RPM complete erected in position as per specification no. FG-FN/EXF	4	Each		
6	Providing recess in brick wall suitable for erection of exhaust fan up to 450 mm sweep complete with grouting of nut, bolts, plaster in hand colour washing to match the colour of the wall for the wall thickness of 150 mm.	4	Each		
7	Supplying & erecting 22 SWG G.I sheet metal cawl sector shaped with 25 x 25 x 3 (mm) angle iron frame, metal mesh to avoid birds entry with necessary material, suitable for exhaust fan of 450 mm as per specification no FG-FAS/MSC	4	Each		
8	Supplying and erecting D.O.L. Starter 400V. 3 phase, 50 cycles with no volt coil and overload element with necessary materials and connected to supply upto 7.5 H.P.	3	Each		
9	Supplying and erecting LED street light fitting suitable above 26W to 36W lamp, including lamp, with PF > 0.95 class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete as per specification No FG-ODF/FLS2.	3	Each		
10	Supplying and erecting street light Wall bracket made from 25 mm. dia 'B' class G.I. pipe 1.2 m in total length complete as per specification no. FG-BKT/WB	3	Each		

Terms & Condition :-

- 1) The quoted rates shall be firm and inclusive of all taxes, duties, transportation up to site except GST.
- 2) Quotation shall be valid for 60 days from the date of submission of quotations.
- 3) The work shall start immediately after issue of work order & complete within 30 days from the date of work order.

- 4) The payment will be made after satisfactory completion of work & as per availability of funds.
- 5) Copy of PAN card shall be submitted.
- 6) GST for the work will be paid after submitting documentary evidence of GST Paid and deduction will be as per prevailing GR.
- 7) Executive Engineer reserve right cancel or reject the quotations at any stage without assigning any reason thereof.



(T.A. Gaidhane)
Executive Engineer
Vidarbha Hydro Electric & Lift Irrigation
Division, Bhandara

- Copy on:-
- 1) Superintending Engineer, Vidarbha Hydro Electric & Lift Irrigation Circle,
Nagpur for information please.
 - 2) Notice Board of the Division office, Bhandara.